wilmar MNA Serang	**Project :**	ETP PLANT	**Page :**	2 of 2	E&I PROJECT
	Project Code :		**Date :**	30/10/2018	
	Document Name :	ELECTRICAL LOAD LIST			
	Document No :	BED-DOC-ETP-EI-02			REV.0

Electromotor Data															**Cable Connection**							**Panel**	
No.	Original Tag	Wilmar Tag	Designation	Requirment		Starting	Rated Power (KW)	Nom. Current (A)	PF	Poles/Rated Speed rpm	Rated Voltage (V)	Motor Brand	Motor Type/Model	EEX Proof Req.	Index Protection	Type	Size (sqmm)	Pulling Quantity (Set)	Length / Pulling (m)	Total Length(m)	Gland Size (mm)	Connecting	Remarks
				continouse	standby																		
1	CAF-1811	CAF1811	CAF Aerator	1		DOL	2,2	4,1			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
2	AG-1810A	AG1810A	Agitator for Reactor	1		DOL	0,75	1,4			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
3	AG-1810B	AG1810B	Agitator for Reactor	1		DOL	0,75	1,4			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
4	SKM-1811	SKM1811	CAF Skimmer	1		DOL	0,55	1,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
5	P1801A	PU1801A	Accident tank pump	1		DOL	5,5	10,3			380 V 50 Hz 3Ph			N/A		NYY-FR	4x4mm	1	80	80	M20	MCC-22B2	
6	P1801B	PU1801B	Accident tank pump		1	DOL	5,5	10,3			380 V 50 Hz 3Ph			N/A		NYY-FR	4x4mm	1	80	80	M20	MCC-22B2	
7	P1802A	PU1802A	EQ tank pump	1		DOL	5,5	10,3			380 V 50 Hz 3Ph			N/A		NYY-FR	4x4mm	1	80	80	M20	MCC-22B2	
8	P1802B	PU1802B	EQ tank pump		1	DOL	5,5	10,3			380 V 50 Hz 3Ph			N/A		NYY-FR	4x4mm	1	80	80	M20	MCC-22B2	
9	BW-1830A	BW1830A	Blower-1	1		DOL	45	83,9			380 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	80	80	M32	MCC-22B2	As Per PSA Result
10	BW-1830B	BW1830B	Blower-2	1		DOL	45	83,9			380 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	80	80	M32	MCC-22B2	As Per PSA Result
11	BW-1830C	BW1830C	Blower-3		1	DOL	45	83,9			380 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	80	80	M32	MCC-22B2	As Per PSA Result
12	FTP-1851	FTP1851	Filter Press	1		OIG	4,0	7,5			380 V 50 Hz 3Ph			N/A		NYY-FR	4x2.5mm	1	80	80	M20	MCC-22B2	
13	PU-1852A	PU1852A	Dewatering Pump	1		DOL	7,5	14,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x6mm	1	80	80	M25	MCC-22B2	
14	PU-1852B	PU1852B	Dewatering Pump		1	DOL	7,5	14,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x6mm	1	80	80	M25	MCC-22B2	
15	PU-1813	PU1813	H2SO4 Dosing Pump	1		VFD	0,2	0,4			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
16	PU-1812A	PU1812A	Lime Pump	1		DOL	2,2	4,1			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
17	PU-1812B	PU1812B	Lime Pump		1	DOL	2,2	4,1			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
18	AG-1812A	AG1812A	Agitator	1		DOL	0,75	1,4			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
19	AG-1812B	AG1812B	Agitator		1	DOL	0,75	1,4			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
20	PU-1814A	PU1814A	PAC Pump	1		VFD	0,55	1,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
21	PU-1814B	PU1814B	PAC Pump		1	VFD	0,55	1,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
22	AG-1814A	AG1814A	Agitator	1		DOL	0,75	1,4			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
23	AG-1814B	AG1814B	Agitator		1	DOL	0,75	1,4			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
24	PU-1815A	PU1815A	PAM Pump	1		VFD	0,55	1,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
25	PU-1815B	PU1815B	PAM Pump		1	VFD	0,55	1,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
26	AG-1815	AG1815	Agitator	1		DOL	0,75	1,4			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
27	PU-1831A	PU1831A	Clarifier Pump	1		DOL	5,5	10,3			380 V 50 Hz 3Ph			N/A		NYY-FR	4x4mm	1	80	80	M20	MCC-22B2	
28	PU-1831B	PU1831B	Clarifier Pump		1	DOL	5,5	10,3			380 V 50 Hz 3Ph			N/A		NYY-FR	4x4mm	1	80	80	M20	MCC-22B2	
29	PU-1841A	PU1841A	Clarifier Pump	1		DOL	5,5	10,3			380 V 50 Hz 3Ph			N/A		NYY-FR	4x4mm	1	80	80	M20	MCC-22B2	
30	PU-1841B	PU1841B	Clarifier Pump		1	DOL	5,5	10,3			380 V 50 Hz 3Ph			N/A		NYY-FR	4x4mm	1	80	80	M20	MCC-22B2	
31			Biocide dosing pump	1		DOL	0,55	1,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
32			Biocide dosing pump		1	DOL	0,55	1,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
33	SCP-1831	SCP1831	Scrapper (Aerobic Clarifier)	1		DOL	0,75	1,4			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
34	SCP-1841	SCP1841	Scrapper (Final Clarifier)	1		DOL	0,75	1,4			380 V 50 Hz 3Ph			N/A		NYY-FR	4x1.5mm	1	80	80	M20	MCC-22B2	
				22	12				**75 % Max Load**														
	Total Connected Load			**B+C=**		**A**	**215,40**	**401,54**	**kW**	**A**													
	Max Load					**B**	**135,55**	**252,69**	**101,7**	**189,5**													
	Stand by Load					**C**	**79,85**	**148,85**															