wilmar	**Project :**	FRACTINATION PLANT IV 60	**Page :** 5 of 5	E&I PROJECT
	Project Code :		**Date :** 01/08/2018	
	Document Name :	ELECTRICAL LOAD LIST		
MNA Serang	**Document No :**	BED-DOC-FRC1-EI-01		REV.3

				Electromotor Data										Cable Connection						Panel	
No.	Original Tag	Wilmar Tag	Designation	equirme		Starting	Rated Power (KW)	Nom. Current (A)	PF	Poles/Rated Speed rpm	Rated Voltage (V)	Motor Brand	Motor Type/Model	EEX Proof Req.	Index Protection	Type	Size (sqmm)	Pulling Quantity (Set)	Length / Pulling (m)	Total Length(m)	Gland Size (mm)	Connecting	Remarks
				continoue	standby																		
FRACT#1 LUA																							
3	PU-1401A	PU1401A	Warm Tank to Chiller & Cold Tank Pump	1		S/S	110	205,1			3phase, 380V, 50Hz			N/A		NYY-FR	4x95mm	1	100	100	M50	MCC-25C3	Before : 90, Update 18/12/15
4	PU-1401B	PU1401B	Warm Tank to Chiller & Cold Tank Pump	1		S/S	110	205,1			3phase, 380V, 50Hz			N/A		NYY-FR	4x95mm	1	100	100	M50	MCC-25C3	Before : 90, Update 18/12/15
5	PU-3012A	PU3012A	Cooling Water Circulating Chiller Pump	1		S/S	132	246,1			3phase, 380V, 50Hz			N/A		NYY-FR	4x120mm	1	100	100	M63	MCC-25C3	
6	PU-3012B	PU3012B	Cooling Water Circulating Chiller Pump	1		S/S	132	246,1			3phase, 380V, 50Hz			N/A		NYY-FR	4x120mm	1	100	100	M63	MCC-25C3	
7	CT-3012A	CT3012A	Fan Cooling Tower Chiller	1		VFD	45	83,9			3phase, 380V, 50Hz			N/A		NYY-FR	4x35mm	1	100	100	M32	MCC-25C3	
8	CT-3012B	CT3012B	Fan Cooling Tower Chiller	1		VFD	45	83,9			3phase, 380V, 50Hz			N/A		NYY-FR	4x35mm	1	100	100	M32	MCC-25C3	
9	PU-1402A	PU1402A	Chilled Water Tank to Fract#1 & Warm Tank Pump		1	S/S	132	246,1			3phase, 380V, 50Hz			N/A		NYY-FR	4x120mm	1	100	100	M63	MCC-25C3	
10	PU-1402B	PU1402B	Chilled Water Tank to Fract#1 & Warm Tank Pump	1		S/S	132	246,1			3phase, 380V, 50Hz			N/A		NYY-FR	4x120mm	1	100	100	M63	MCC-25C3	
			Sub Total	7	1																		
									75 % Max Load														
			Total Connected Load	**B+C=**		**A**	**838,0**	**1.562,2**	**kW**	**A**													
			Max Load			**B**	**706,00**	**1316,09**	**529,5**	**987,1**													
			Stand by Load			**C**	**132,00**	**246,07**															