wilmar	**Project :**	FRACTINATION PLANT IV 56	**Page :** 3 of 4	E&I PROJECT
	Project Code :		**Date :** 30/10/2018	
	Document Name :	ELECTRICAL LOAD LIST		
MNA Serang	**Document No :**	BED-DOC-FRC2-EI-01		REV.0

				Electromotor Data												**Cable Connection**						**Panel**	
No.	Original Tag	Wilmar Tag	Designation	Requirment continoue	Requirment standby	Starting	Rated Power (KW)	Nom. Current (A)	PF	Poles/Rated Speed rpm	Rated Voltage (V)	Motor Brand	Motor Type/Model	EEX Proof Req.	Index Protection	Type	Size (sqmm)	Pulling Quantity (Set)	Length / Pulling (m)	Total Length(m)	Gland Size (mm)	Connecting	Remarks
OSBL																							
1	PU-302A	PU302A	Cooling Water Pump	1		S/S	90	167,8			3phase, 380V, 50Hz					NYY-FR	4x95mm	1	80	80	M50	MCC-26A2	Before : 75, Update 18/12/15
2	PU-302B	PU302B	Cooling Water Pump	1		S/S	90	167,8			3phase, 380V, 50Hz					NYY-FR	4x95mm	1	80	80	M50	MCC-26A2	Before : 75, Update 18/12/15
3	CT-302	CT302	Cooling Tower Package	1		VFD	18,5	34,5			3phase, 380V, 50Hz					NYY-FR	4x16mm	1	80	80	M32	MCC-26A2	
4	PU-602B	PU602B	Condensate Pump	1		DOL	7,5	14,0			3phase, 380V, 50Hz					NYY-FR	4x6mm	1	80	80	M25	MCC-26A2	Before : 11, Update 18/12/15
5	PU-902B	PU-902B	Effluent Pump	1		DOL	7,5	14,0			3phase, 380V, 50Hz					NYY-FR	4x6mm	1	80	80	M25	MCC-26A2	
				5	0				75 % Max Load														
	Total Connected Load			**B+C=**		**A**	**213,5**	**398,0**	**kW**	**A**													
	Max Load					**B**	**213,5**	**398,0**	**160,1**	**298,5**													
	Stand by Load					**C**	**0,0**	**0,0**															