wilmar MNA Serang	**Project :**	REFINERY PLANT IV 56	**Page :** 3 of 3	E&I PROJECT
	Project Code :		**Date :** 30/10/2018	
	Document Name :	ELECTRICAL LOAD LIST		
	Document No :	BED-DOC-REF2-EI-01		REV.0

				Electromotor Data												**Cable Connection**						**Panel**	
No.	Original Tag	Wilmar Tag	Designation	Requirment		Starting	Rated Power (KW)	Nom. Current (A)	PF	Poles/Rated Speed rpm	Rated Voltage (V)	Motor Brand	Motor Type/Model	EEX Proof Req.	Index Protection	Type	Size (sqmm)	Pulling Quantity (Set)	Length / Pulling (m)	Total Length(m)	Gland Size (mm)	Connecting	Remarks
				continoue	standby																		
OSBL																							
1	PU-304A	PU-304A	Pump Cooling Water Refinery #2	1		S/S	132	246,1			380 V 50 Hz 3Ph					NYY-FR	4x120mm	1	80	80	2*M40	MCC-26B2	
2	PU-304B	PU-304B	Pump Cooling Water Refinery #2	1		S/S	132	246,1			380 V 50 Hz 3Ph					NYY-FR	4x120mm	1	80	80	2*M40	MCC-26B2	
3	PU-304C	PU-304C	Pump Cooling Water Refinery #2		1	S/S	132	246,1			380 V 50 Hz 3Ph					NYY-FR	4x120mm	1	80	80	2*M40	MCC-26B2	
4	CT-304A	CT304A	Cooling Tower Refinery #2	1		VFD	30	55,9			380 V 50 Hz 3Ph					NYY-FR	4x25mm	1	80	80	M32	MCC-26B2	
5	CT-304B	CT304B	Cooling Tower Refinery #2	1		VFD	30	55,9			380 V 50 Hz 3Ph					NYY-FR	4x25mm	1	80	80	M32	MCC-26B2	
6	PU-901B	PU901B	Effluent Pump	1		DOL	7,5	14,0			380 V 50 Hz 3Ph					NYY-FR	4x6mm	1	80	80	M25	MCC-26B2	
7	PU-601B	PU601B	Condensate Pump	1		DOL	7,5	14,0			380 V 50 Hz 3Ph					NYY-FR	4x6mm	1	80	80	M25	MCC-26B2	Before : 11. Uodate 18/12/15
LUA REF#2																							
1	PU-1901B	PU1901B	MNA Fuel Distribution Pump	1		DOL	1,10	2,05			380 V 50 Hz 3Ph					NYY-FR	4x1,5mm	1	80	80	M20	MCC-26B2	
2	PU-2023B	PU2023B	Caustic Soda Pump	1		DOL	7,5	13,98			380 V 50 Hz 3Ph					NYY-FR	4x6mm	1	80	80	M25	MCC-26B2	Before : 15, Update 18/12/15
3	PU-2025B	PU2025B	Cintric Acid Pump	1		DOL	5,5	10,25			380 V 50 Hz 3Ph					NYY-FR	4x4mm	1	80	80	M20	MCC-26B2	
4	PU-1801B	PU1801B	Chemical Distribution Pump	1		DOL	7,5	13,98			380 V 50 Hz 3Ph					NYY-FR	4x6mm	1	80	80	M25	MCC-26B2	Before : 11, Update 18/12/15
5	MV610A2	RL2610B	Rotary Valve/(Blower) for BE	1		DOL	45	83,9			380 V 50 Hz 3Ph					NYY-FR	4x35mm	1	80	80	M32	MCC-26B2	
6	MV610C	RL2610C	Rotary Valve/(Blower) for FA	1		DOL	22,0	41,0			380 V 50 Hz 3Ph					NYY-FR	4x16mm	1	80	80	M32	MCC-26B2	
				6	1					**75 % Max Load**													
	Total Connected Load			**B+C=**		**A**	559,6	878,0	**kW**	**A**													
	Max Load					**B**	**427,60**	**631,95**	**320,7**	**474,0**													
	Stand by Load					**C**	**132,00**	**246,07**															