wilmar		**Project :**	Tank farm MNA														**Page :**	3 of 3		E&I PROJECT				
		Project Code :															**Date :**	30/10/2018						
		Document Name :	ELECTRICAL LOAD LIST																					
MNA Serang		**Document No :**	BED-DOC-TFR-EI-01																			REV.0		
Electromotor Data															**Cable Connection**							**Panel**		
No.	Original Tag	Wilmar Tag	Designation	Requirment		Starting	Rated Power (KW)	Nom. Current (A)	PF	Poles/Rated Speed rpm	Rated Voltage (V)	Motor Brand	Motor Type/Model	EEX Proof Req.	Index Protection	Type	Size (sqmm)	Pulling Quantity (Set)	Length / Pulling (m)	Total Length(m)	Gland Size (mm)	Connecting	Remarks	
				continoue	standby																			
Unloading Station																								
1	PU-2401A		S-CPO Unloading Pump A	1		DOL	37	69,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	80	80	M32	MCC-27A1		
2	PU-2401B		S-CPO Unloading Pump B		1	DOL	37	69,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	80	80	M32	MCC-27A1		
3	PU-2402A		N-CPO Unloading Pump A	1		DOL	37	69,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	80	80	M32	MCC-27A1		
4	PU-2402B		N-CPO Unloading Pump B		1	DOL	37	69,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	80	80	M32	MCC-27A1		
5	PU-2403A		CPKO Unloading Pump A	1		DOL	37	69,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	80	80	M32	MCC-27A1		
6	PU-2403B		CPKO Unloading Pump B		1	DOL	37	69,0			381 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	80	80	M32	MCC-27A1		
									75 % Max Load															
	Total Connected Load			**B+C=**		**A**	**222**	**413,841**	**kW**	**A**														
	Max Load					**B**	**111,00**	**206,92**	**83,3**	**155,2**														
	Stand by Load					**C**	**111,00**	**206,92**																