wilmar MNA Serang	**Project :**	Hydrogen #2 (100 TPD)	**Page :** 3 of 3	E&I PROJECT
	Project Code :		**Date :** 01/08/2018	
	Document Name :	ELECTRICAL LOAD LIST		
	Document No :	BED-DOC-HYD2-EI-01		REV.0

				Electromotor Data												**Cable Connection**						**Panel**	
No.	Original Tag	Wilmar Tag	Designation	Requirment continouse	Requirment standby	Starting	Rated Power (KW)	Nom. Current (A)	PF	Poles/Rated Speed rpm	Rated Voltage (V)	Motor Brand	Motor Type/Model	EEX Proof Req.	Index Protection	Type	Size (sqmm)	Pulling Quantity (Set)	Length / Pulling (m)	Total Length(m)	Gland Size (mm)	Connecting	Remarks
OSBL																							
1	PU-309A	PU309A	Cooling Water Pump	1		DOL	45	83,9			380 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	100	100	M32	MCC-29A4	Before 75
2	PU-309B	PU309B	Cooling Water Pump	1		DOL	45	83,9			380 V 50 Hz 3Ph			N/A		NYY-FR	4x35mm	1	100	100	M32	MCC-29A4	Before 75
3	CT-309	CT309	Cooling Tower	1		VFD	15	28,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x10mm	1	100	100	M25	MCC-29A4	
4	PU-3013C	PU3013C	Cooling Water Pump Wica Dirty	1		DOL	7,5	14,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x6mm	1	100	100	M25	MCC-29A4	Before PU-3013B
5	PU-905B	PU905B	Effluent Pump	1		DOL	7,5	14,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x6mm	1	100	100	M25	MCC-29A4	
6	PU-607B	PU607B	Condensate Pump	1		DOL	7,5	14,0			380 V 50 Hz 3Ph			N/A		NYY-FR	4x6mm	1	100	100	M25	MCC-29A4	
				6	0					**75 % Max Load**													
	Total Connected Load			**B+C=**		**A**	127,5	237,7		**kW**	**A**												
	Max Load					**B**	**127,5**	**237,7**		**95,6**	**178,3**												
	Stand by Load					**C**	**0,00**	**0,00**															